

September 07, 2007
Request No. D7-08-020

Missouri Department of Transportation
3901 E. 32nd Street
Joplin, MO. 64802

Re: Scope of work for removing existing Well House then build a new Well House,
location at the Nevada Project Office in Nevada, MO.

Existing Well House dimensions are 5' wide x 5' long and over all height including roof is 3'. The roof hinge on one end to access the well equipment and hardware. The existing walls were concrete and the roof was wood structure and Metal skin.

New Well House dimensions need to be close to the same. Treated lumber attached to concrete footing /or floor. Wall framing to 2"x6" with R-30 Insulation in the walls and roof. The outside to be 29 gauge White metal and the inside to be marine grade plywood. The roof section to have hinge on one end for access and a barn latch on the other to keep roof secure.

Contractor responsible to remove and reinstall any hardware attached on the inside walls.

Contractor has to give 2 days notice in the event the water has to shut down due to construction.

Contractor is responsible to provide all necessary material to make it a complete and functional system.

Cleanup and haul off any job material caused in the Well house project.

Contractor to coordinate work with Mike Rinehart 417-448-1184 and Larry Palmer 417-629-3352 before work is to start.