

September 07, 2007
Request No. D7-08-021

Missouri Department of Transportation
3901 E. 32nd Street
Joplin, MO. 64802

Re: Scope of work for removing existing aggregate roofing on East bound and West bound Well Houses then replace with hip roof 2"x 6" framing with 29 gauge brown metal. In the center on each one of these well house roofs is a clear plastic Sky light that will be removed and a removable block out put in its place, this will be incase in the future the pump has to be pulled they can remove some metal then remove this block and pull the pump.

The metal to be attached by roof screws.

Roof over hang to be 2".

Trim and fascia metal to be brown also

Contractor is responsible to provide all necessary material to make it a complete and functional system.

Cleanup and haul off any job material caused in the Well house project.

Contractor to coordinate work with Randy Washam 417-466-2401 and Larry Palmer 417-629-3352 before work is to start.