

## Emergency Power Generator and Scope of Work

- Supply a 60 KW Phase 3 Automatic Standby Generator,
- Liquid Cooled
- 120/208V
- Natural Gas
- Automatic start Transfer Switch installed inside building (Boiler utility room)
- Placed on existing concrete pad, conduit and wire placed through concrete wall to transfer switch
- Electrical work to be done inside building install electrical box, power outlets, lighting,
- Make electrical connection to backup UPS, Security system
- Warranty from installer including service and maintenance
- Contract to be completed within 30 days