



WATCH FOR
ENTERING TRAFFIC

SUMMARY			
DESCRIPTION	QTY	UNIT	
CLASS 1 PULL BOX	6	EA	
2" CONDUIT TRENCHED	875	FT	
1" CONDUIT TRENCHED	200	FT	TOTAL OF 3 RUNS
1.5" CONDUIT FOR SIGN POSTS	45	FT	
2c#12 CABLE	1225	FT	
5c#12 CABLE	100	FT	
1c#14 CABLE- FOR INDUCTIVE LOOPS	800	FT	
2c#14 CABLE	850	FT	
WOOD POLES 35'	2	EA	
INDUCTIVE LOOPS	3	EA	
POWER SUPPLY	1	EA	
RED FLASHING BEACON- STOP SIGN MOUNTED	1	EA	
OVERHEAD FLASHING BEACON	1	EA	
POLE MOUNTED CONTROLLER	1	EA	
TRAFFIC CONTROL	1	LS	
3" PIPE POST 12' LONG W/ 3' BREAKAWAY STUB	4	EA	

