




State	Proj. No.	Sheet No.
MO		

1/2" Ø Machine bolt at cot. 18" cts. use two hex nuts to set gap before concrete placement. Gap may be set anytime up to but not exceeding 2 hours before concrete placement. Cut machine bolt flush with each extrusion after concrete set. Each side has taken initial set.



Longitudinal reinforcing steel applied as that used in the existing joist system and the steel reinforcement in the concrete slab and concrete joist system of the original structure are protected by localized internal vibration.



Note: This drawing is not to scale. Follow dimensions.