



PRESTRESSED CONCRETE MEMBERS FOR BRIDGES FIELD SECTION 1029

1029.1 SCOPE. To establish procedures for the inspection and reporting of precast prestressed bridge members. Reinforcing steel and portland cement concrete for use in prestressed members are to be inspected in accordance with the applicable sections of this Manual.

1029.2 APPARATUS.

- (a) Rule and tape with suitable graduations to accurately measure the material to be inspected.
- (b) OK - MoDOT stamp.
- (c) Weather resistant marking materials.
- (d) Air meter, slump cone, and scoop or small shovel for sampling concrete.
- (e) Concrete thermometer.
- (f) Surface thermometer.
- (g) Field Lab in accordance with Specification Sec 106.4.4.

1029.3 PROCEDURE.

1029.3.1 General. Bridge members vary from project to project and bridge to bridge. The inspector should thoroughly familiarize himself with the plans, specifications and special provisions pertaining to the particular project and bridge members to be inspected prior to fabrication. Specification Sec 1029.6.1 requires the contractor to submit shop drawings for approval to the State Bridge Engineer showing in detail the procedure proposed for the fabrication of the members. Such detail as methods and sequence of stressing and releasing stress in the strands is required to be shown on the shop drawings. The inspector is to become thoroughly familiar with the approved shop drawings.

The inspector shall insure that certifications required by Specification Sec 1029.4 have been submitted and are proper and applicable. There shall be no changes or deviations from the approved plans, drawings, or the specifications without the written approval of the State Construction and Materials Engineer. The inspector should insure that the district Operations Engineer in charge of inspection at the fabricating plant is notified in writing of all such changes. Before any stressing or fabrication begins, the inspector shall review with the fabricator the plans, specifications, and inspection procedures to be used with the objective of avoiding any misunderstanding during the progress of the work. Adequate safety measures shall be taken to prevent injuries to personnel due to the breakage of strands or failure of anchorage devices during the tensioning operations. Inspection shall be refused at any plant where adequate safety measures are not provided and maintained. The inspector shall abide by the safety rules established by the producer, provided that they do not interfere with the inspector's normal duties.



1029.3.2 Materials. The inspector shall insure that only inspected and approved materials are used in the fabrication of prestressed concrete members.

1029.3.2.1 Prestressing tendons shall be uncoated seven-wire low relaxation strands conforming to AASHTO M 203, Grade 270. Prestressing strands may be accepted on the basis of a manufacturer's certification certifying that the material meets the requirements of AASHTO M 203 or M 204, as required by the contract. The certification must be accompanied by three copies of the mill test report giving results of physical tests on the material furnished and, for material meeting the requirements of AASHTO M 204, a complete chemical analysis. The strand may also be accepted based on the observation of physical tests, and for material meeting the requirements of AASHTO M 204, a mill test report giving a complete chemical analysis. Regardless of the method of acceptance used, the contractor shall furnish three copies of the stress-strain curve representative of the lot to be used. The inspector shall carefully examine all required certifications and material to insure that they are applicable and show conformance with the specifications. The certifications shall show the lot number and the material shall be tagged for identification purposes. Samples for physical testing shall be obtained and tested at the manufacturer's plant or an approved commercial testing laboratory in the presence of Department personnel. Prestressing strand may be submitted to the Central Laboratory at the discretion of the district Operations Engineer. When strand is accepted by certification, a minimum of one check sample per month of each size for each manufacturer of strand being used shall be submitted to the Laboratory for testing. A sample of prestressing strand shall consist of two pieces of strand, each a minimum of 5 feet [1500 mm] in length. The ends of the strand shall be tied, clamped, fused, or otherwise secured to prevent unwinding or fraying during shipment. All pertinent information should be reported through SiteManager.

1029.3.2.2 Structural steel and high-tensile strength alloy bars are accepted on the basis of field inspection and manufacturer's certification stating that the material meets the requirements of the specifications. The certification shall be accompanied by three copies of the mill test report giving chemical analysis and results of physical tests on the material furnished. The inspector shall carefully examine the certifications and the material to insure that they are applicable and show compliance with the specifications. The certification shall show the lot number and the material shall be tagged for identification purposes. Field inspection shall consist of measurements to determine compliance with the dimensions shown on the plans.

1029.3.3 Equipment. Prestressing equipment, end anchorages, and concrete testing equipment shall be carefully examined by the inspector to insure that the requirements of Specification Sec 1029.5 are met. Calibration of the gauge will be accomplished with the gauges connected to the jacking system to be used in the prestressing operation. The load shall be acting on the ram of the jack and in the same direction as during the tensioning operation. The inspector shall be certain that the proper graphs or tables for the gauges and jacks being used comply with the requirements of Specification Sec 1029.5.1. Pressure gauges should have a full capacity of approximately twice their normal working pressure. The loads to be gauged should not be less than one-fourth or more than three-fourths of the total graduated capacity unless calibration data clearly establish consistent accuracy over a wider range. The gauge pointer on hydraulic gauges must remain steady and not fluctuate until the jacking load can be read and released from the tendon.



1029.3.4 Forms. The inspector shall insure that forms and formwork comply with the applicable requirements of Specification Sec 1029.6.2. Casting beds shall be checked periodically for deviations from a plane surface sufficient to cause irregularities in the bearing area of the beams or other irregularities that may approach or exceed established tolerances. Forms, bulk heads, spacers, spreader bars, templates, and other equipment having a bearing upon accuracy of dimensions and trueness of lines of the completed beams shall be checked periodically. They shall be clean and free of hardened concrete. Extreme care shall be exercised to prevent form oil from coming into contact with the strands and reinforcement. Hold-up and hold-down devices must be attached in such a manner as to maintain the specified center-to-center spacing of strands in both the vertical and horizontal directions. Clamps, bolts, or other devices connecting the bulk-head to the side forms, inserts, blockouts, etc., should be capable of being removed or loosened before steam curing is applied. The casting bed should have a concrete deck on which the forms may be adequately centered, aligned and leveled to the same plane.

1029.3.5 Stressing Requirements. The inspector shall insure that the prestressing tendons are accurately placed and securely held during the placing and curing of concrete. All tensioning of strands shall be performed in the presence of the inspector. No tensioning of strands shall be permitted when the temperature of the strand is below 30 F [-1 C]. In all methods of tensioning, the stress induced in the prestressing strand shall be measured both by jacking gauges and by elongation. Tensioning may be done to calculated gauge pressure using elongation as a check. Elongation should be measured to within 1/16 inch [1 mm]. Pressure gauge readings at the time of the measured net elongation should be within ± 5 percent of the calculated gauge reading for that particular elongation. If the gauge readings vary more than 5 percent from their calculated reading, all work should be stopped and corrections made before proceeding. Elongations shall make appropriate allowance for temperature, chuck slippage and relaxation of the anchorage. Jacking pressure shall make appropriate allowance for temperature, live-end chuck-slippage, and relaxation of the anchorage (or bed shortening for a self-stressing bed). Live-end chuck slippage shall be determined as described in Section 705.3.5.1. Elongation shall be within ± 5 percent of that specified upon completion of stressing operations. Specified elongation is calculated using the design load as shown on the approved shop drawings. Independent references should be established adjacent to each anchorage to indicate any yielding or slippage that may occur between the time of initial stressing and final release of cables. Stressing of strands may be from one end unless otherwise indicated in the contract or on the approved shop drawings. Draped strands may be tensioned by either partially jacking from the end of the bed followed by raising or lowering the strands to their final position or entirely by jacking with the strands being held in their draped position during the jacking operation. When the strands are tensioned in their draped position, they should be supported by free-turning rollers at all hold-up and hold-down points. A discrepancy of more than 5 percent between stresses in the strand or tendon as computed from the elongation measurement and those indicated by gauge readings should be cause for jacking from both ends. When attempts by jacking at both ends fail to attain the required elongation, the number of deflection points on the bed shall be reduced or the hardware shall be improved to reduce friction. When strands are deflected after partial tensioning, the strands should be raised or depressed simultaneously at all points or in an approved specific sequence. Several members may be cast in one continuous line, provided that all members are fabricated without undue intervening delay. The time intervening between the casting of the first and last member on a bed shall not exceed 4 days unless otherwise permitted by the engineer. When the temperature at the time of tensioning is such that correction must be made to compensate for change in strand stresses, all members on the bed shall be cast in a continuous pour.



The tension in the strand as determined from the elongation at the time of placing concrete shall be within 5 percent of that required. The amount of stress to be given each strand shall be as shown on the plans. Tensioning shall be by either the single strand or multi-strand jacking method. Each strand shall be brought to a uniform initial tension as shown in the tensioning schedule on the approved shop drawings. The initial tension on each strand shall be accurately measured by a dynamometer or other approved means. The initial tension should be within 50 pounds [200 N] or 5 percent of that required, whichever is the larger. The initial tension shall be between 5 and 25 percent of the design load as shown on the approved shop drawings. The initial tension should be enough to remove the slack from the strand so that a point can be established for elongation measurement that is valid but not too excessive as to eliminate too much of the elongation which will take place to reach the final load. The same jack used for single strand tensioning may be used for initial tensioning provided it is equipped with proper gauging systems for measuring the initial tension. Measurement of elongation shall not begin until initial tensioning has been completed. When the initial tensioning force is applied to the tendon, reference points for measuring the elongation due to additional tensioning forces must be established. One method of establishing reference points for elongation is use of masking tape. Short sections of tape are wrapped around the strand a predetermined distance from the end anchorage while the initial stress is being applied. Further stress measurements can then be made from the edge of the tape. Any other marking device that provides a sharply defined reference line could be used. Strands passing through stirrups, spirals, headers, hold-ups, or hold-downs should be carefully inspected to guard against unusual bindings which would result in substantial restraint. When excessive friction is suspected and especially when tensioning strand in the draped position, checks should be made to insure that tension is uniform throughout the bed. One method is using masking tape to mark a known length of strand near each end of the bed and one near the center. These lengths should be as long as practical. The elongation in these predetermined sections should be within 5 percent of that specified when computed using the design load as shown on the approved shop drawings.

1029.3.5.1 An example for verifying that the elongation upon completion of the stressing operations is within ± 5 percent of that specified is as follows:

Specified elongation = PL/AE

Where:

P = Design load as shown on the plans

L = Distance in inches from anchorage to reference point

A = Area of one strand

E = Modulus of elasticity of steel strand determined from the test report

Elongation upon completion of stressing = Seated Elongation - 1/2 measured anchorage movement (or bed shortening for self stressing beds) - measured dead end chuck slippage.

% Deviation = $\frac{EL - SE}{SE} \times 100$

Where:

EL = Elongation upon completion of stressing

SE = Specified elongation



ENGLISH UNITS

For this example:

P = 31,000 lbf
L = 3,600 inches
A = 0.153 sq. inches
E = 28,300,000 psi
Seated elongation = 26.00 inches
1/2 measured anchorage movement = 0.25 inches
Measured dead end chuck slippage = 0.125 inches

Therefore:

$$\text{Specified Elongation (SE)} = \frac{31000 \times 3600}{.153 \times 28,300,000} = 25.774 \text{ in.}$$

$$\text{Elongation upon completion of stressing (EL)} = 26.00 - .25 - .125 = 25.625 \text{ inches}$$

$$\% \text{ Deviation} = \frac{25.625 - 25.774}{25.774} \times 100 = -0.6\%$$

A negative % deviation indicates the strand is understressed.

A positive % deviation indicates the strand is overstressed.

SI (METRIC) UNITS

For this example:

P = 137800 N
L = 91500 mm
A = 100 mm²
E = 20000 MPa
Seated elongation = 660 mm
1/2 measured anchorage movement = 6 mm
Measured dead end chuck slippage = 3 mm

Therefore:

$$\text{Specified Elongation(SE)} = \frac{137800 \times 91500}{100 \times 20000} = 630$$

$$\text{Elongation upon completion of stressing (EL)} = 660 - 6 - 3 = 651 \text{ mm}$$

$$\% \text{ Deviation} = \frac{651 - 630}{630} \times 100 = -3.3 \%$$

A negative % deviation indicates the strand is understressed.

A positive % deviation indicates the strand is overstressed.

1029.3.5.2 Live End Chuck Slippage. One method of determining the amount of chuck slippage is to place Styrofoam doughnuts or similar devices on the strand inside the anchorages. These devices will ride the strand during tensioning until stopped by the pull



plate then ride the strand back as slippage occurs. By measuring the distance between the pull plate and the doughnut the amount of slippage can be determined.

1029.3.6 Prestressing Steel Strand. All strands must be free of contaminants such as dirt, oil, paint, wax, corrosion, or other foreign material that may prevent bond between the strands and the concrete. Strands that have been previously tensioned one time may be used providing that they are properly identified, have not been stressed in excess of 80 percent of ultimate strength, and comply with all the applicable requirements of the specifications. The use of prestressing strands having kinks, bends, nicks, or other defects shall not be permitted. A light coating of rust shall not be cause for rejection providing that the loose rust is removed and the surface of the strands is not visibly damaged. Pretensioned steel should always be checked for substances injurious to bond development after tensioning. Tensioned strands should be protected against excessive temperatures such as those produced by torches, welding equipment, or sparks. The strands must be positioned within the dimensions shown on the approved shop drawings. Strands tensioned as a group shall have the same initial tension, be from the same manufacturer, and have essentially the same modulus of elasticity.

1029.3.6.1 Strand Splices. One approved splice per strand may be permitted provided the splices are located outside of the prestressed member. For single strand tensioning, the number of strands per bed that may be spliced is not restricted. When multi-strand jacking is used, either all strands should be spliced or not more than 10 percent of the strands should be spliced. Spliced strands shall be similar in physical properties, from the same manufacturer, and shall have the same twist or lay. If two opposing lays are joined, the splice will rotate resulting in considerable stress loss in the strand.

1029.3.6.2 Wire Failure. Wire failures may be accepted provided not more than one wire in any strand is broken and the area of broken wires does not exceed 2 percent of the total area of the strands. Strands with broken wire should be pulled to the same elongation but not the same load as strands with no broken wire. Stressing to the same load will result in stresses approaching or exceeding 80 percent of the ultimate strength of the strand. If a wire fails during stressing and the elongation is exceeded, a check should be made using the reduced area to insure that the resulting elongation has not produced stress in excess of 80 percent of the ultimate strength of the strand. Double Tee Girders are to be considered as a unit.

1029.3.6.3 Elongation Computations (English Units). It is the responsibility of the contractor to compute the required elongation and furnish a copy of the computations to the inspector. It is the inspector's responsibility to check the accuracy of these computations. The length of the strand to be used in calculating elongations shall be the actual length of the strand along its trajectory between the fixed anchorage and the reference point at the jacking end of the strand. It is imperative that the actual dimensions of the bed layout and locations of hold-up and hold-down points agree with the dimensions shown on the approved shop drawings within allowable tolerances. Stress losses due to slippage of strand anchorages and movement of anchorage abutments must be accounted for in the elongation computations. Occasional checks for slow slippage of the chucks should be made to insure that the required stresses are being maintained. The following example is a typical problem:

$$\begin{aligned}\epsilon &= \text{elongation in inches} \\ &= PL/AE\end{aligned}$$



P = tension force in pounds

L = distance in inches from anchorage to reference point

A = Area of one strand

E = modulus of elasticity of steel strand determined from the test report 28,300,000 psi

Initial Tension = 3000 lbf.

For this problem:

P = 31,000 lbf (Total) - 3,000 lbf (Initial)
= 28,000 lbf (Net)

L = 300 ft. x 12 in./ft
= 3600 in.

A = 0.153 sq. in.

$\epsilon = \frac{28,000 \times 3600}{0.153 \times 28,300,000}$
= 23.28 in.

0.37 in. slippage in strand anchorages (0.31 in live end slippage + 0.06 dead end slippage) and 0.25 in. one-half of total horizontal movement of anchoring abutments are assumed based on past plant experience. Then, total elongation required after initial tensioning to leave 31,000 lbs. in the strand equals:

$$23.28 \text{ in.} + 0.37 \text{ in.} + 0.25 \text{ in.} = 23.90 \text{ in.}$$

Changes in the ambient temperature after steel tensioning will result in stress changes in the tendons. If steel is stressed in a cold atmosphere and warm concrete is placed around it, there will be a reduction in the tension due to the thermal expansion of the steel. Corrections for steel temperature variation in excess of 30 F shall be made by initial overstressing. At the engineer's discretion, corrections may be required for lower temperature variations. Where required overstressing exceeds 80 percent of the ultimate strength of the strand, the State Construction and Materials Engineer, should be consulted. The amount of strand under tension which will not be subjected to elevated temperatures while the concrete is undergoing its initial set should be considered in the computations. Thermal correction is not used on self-stressing beds. A self-stressing bed is a bed where abutments are not fastened to footings, allowing horizontal movement. This will allow abutments and forms to expand or contract at the same rate as the strand.

An example of computations for temperature correction is as follows:

Assume for the previous example of elongation computations that the strands are stressed at a strand temperature of 35 F and that the concrete at placement was expected to have a temperature of 77 F.



$$\begin{aligned} P &= 31,000 \text{ lbf. (Total)} - 3,000 \text{ lbf. (Initial)} \\ &= 28,000 \text{ lbf. (Net)} \end{aligned}$$

$$\begin{aligned} L &= 300 \text{ ft.} \times 12 \text{ in./ft} \\ &= 3600 \text{ in.} \end{aligned}$$

$$A = 0.153 \text{ sq. in.}$$

$$\epsilon = 23.28 \text{ in.}$$

Length of strand which is not subject to elevated temperature from either concrete or applied heat = 50 ft. = 600 inches

$$\text{Thermal coefficient of expansion of steel} = 0.0000065 \text{ in./in./}^{\circ}\text{F.}$$

$$\begin{aligned} \text{Total length change strand due to temperature elevation} &= 0.0000065 \text{ in.} \times (3600 \text{ in.} - 600 \text{ in.}) \times (77 \text{ F} - 35 \text{ F}) \\ &= 0.82 \text{ in.} \end{aligned}$$

$$\begin{aligned} \text{Total elongation} &= 23.28 \text{ in.} + 0.82 \text{ in.} \\ &= 24.10 \text{ in.} \end{aligned}$$

$$\begin{aligned} \text{Then total elongation necessary to leave 31,000 lbf in strand} &= 24.10 \text{ in.} + 0.25 \text{ in.} + 0.37 \text{ in.} \\ &= 24.72 \text{ in.} \end{aligned}$$

An example of computations for force when stressing:

$$\begin{aligned} \text{Force per in.} &= P/\epsilon = 28,000/23.28 \\ &= 1202.75 \text{ lbf./in.} \end{aligned}$$

Force for live end slippage + temperature correction + 1/2 anchorage movement (or bed shortening) = $(0.31 + 0.82 + .25) \times 1202.75 = 1660 \text{ lbs.}$

$$\begin{aligned} \text{Total load} &= \text{specified load} + \text{force for live end slippage} + \text{temperature correction} = 31,000 + 1660 \\ &= 32,660 \text{ lbf} \end{aligned}$$

Similar corrections should be made if stressing is done on a very warm day. The temperature of the steel on beds may approximate 110 F on a warm day, while the concrete temperature may be in the range of 70 F to 75 F. The resulting reduction in the steel temperature will result in an increase of tensile stresses in the steel. One is usually able to predict the temperature of the fresh concrete with sufficient accuracy to calculate the temperature change expected on the steel at the time the concrete is placed.

1029.3.6.3(M) Elongation Computations (Metric (SI) Units). (This example is not a numeric duplicate of the English version.) It is the responsibility of the contractor to compute the required elongation and furnish a copy of the computations to the inspector. It is the inspector's responsibility to check the accuracy of these computations. The length of the strand to be used in calculating elongations shall be the actual length of the strand along



its trajectory between the fixed anchorage and the reference point at the jacking end of the strand. It is imperative that the actual dimensions of the bed layout and locations of hold-up and hold-down points agree with the dimensions shown on the approved shop drawings within allowable tolerances. Stress losses due to slippage of strand anchorages and movement of anchorage abutments must be accounted for in the elongation computations. Occasional checks for slow slippage of the chucks should be made to insure that the required stresses are being maintained. The following example is a typical problem:

$$\begin{aligned}\varepsilon &= \text{elongation in millimeters} \\ &= PL/AE\end{aligned}$$

$$P = \text{tension force in Newtons}$$

$$L = \text{distance in millimeters from anchorage to reference point}$$

$$A = \text{Area of one strand}$$

$$E = \text{modulus of elasticity of steel strand determined from the test report 200000 MPa}$$

$$\text{Initial Tension} = 13300 \text{ Newtons.}$$

For this problem:

$$\begin{aligned}P &= 137800 \text{ N (Total)} - 13300 \text{ N (Initial)} \\ &= 124700 \text{ N (Net)}\end{aligned}$$

$$\begin{aligned}L &= 91.5 \text{ m} \times 1000 \text{ mm/m} \\ &= 91500 \text{ mm}\end{aligned}$$

$$A = 100 \text{ mm}^2$$

$$\begin{aligned}\varepsilon &= \frac{124700 \times 91500}{100 \times 200000} \\ &= 570 \text{ mm}\end{aligned}$$

10 mm slippage in strand anchorages (8 mm in live end slippage + 1.5 mm dead end slippage) and 6 mm one-half of total horizontal movement of anchoring abutments are assumed based on past plant experience. Then, total elongation required after initial tensioning to leave 138000 N in the strand equals:

$$570 \text{ mm} + 10 \text{ mm} + 6 \text{ mm} = 586 \text{ mm}$$

Changes in the ambient temperature after steel tensioning will result in stress changes in the tendons. If steel is stressed in a cold atmosphere and warm concrete is placed around it, there will be a reduction in the tension due to the thermal expansion of the steel. Corrections for steel temperature variation in excess of 15 C shall be made by initial overstressing. At the engineer's discretion, corrections may be required for lower temperature variations. Where required overstressing exceeds 80 percent of the ultimate strength of the strand, the State Construction and Materials Engineer, should be consulted.



The amount of strand under tension which will not be subjected to elevated temperatures while the concrete is undergoing its initial set should be considered in the computations. Thermal correction is not used on self-stressing beds. A self-stressing bed is a bed where abutments are not fastened to footings, allowing horizontal movement. This will allow abutments and forms to expand or contract at the same rate as the strand.

An example of computations for temperature correction is as follows:

Assume for the previous example of elongation computations that the strands are stressed at a strand temperature of 2 C and that the concrete at placement was expected to have a temperature of 25 C.

$$P = 138000 \text{ N (Total)} - 13300 \text{ N (Initial)}$$

$$= 124700 \text{ N (Net)}$$

$$L = 91.5 \text{ m} \times 1000 \text{ mm/m}$$

$$= 91440 \text{ mm}$$

$$A = 100 \text{ mm}^2$$

$$\varepsilon = 570 \text{ mm}$$

Length of strand which is not subject to elevated temperature from either concrete or applied heat = 15.24 m = 15240 mm

$$\text{Thermal coefficient of expansion of steel} = 0.0000117 \text{ mm/mm/}^{\circ}\text{C}$$

$$\text{Total length change strand due to temperature elevation} = 0.0000117 \times (91500 - 15240) \times (25 \text{ C} - 2 \text{ C})$$

$$= 20 \text{ mm}$$

$$\text{Total elongation} = 570 \text{ mm} + 20 \text{ mm}$$

$$= 590 \text{ mm}$$

$$\text{Then total elongation necessary to leave } 137888 \text{ N in strand} = 590 \text{ mm} + 6 \text{ mm} + 10 \text{ mm}$$

$$= 606 \text{ mm}$$

An example of computations for force when stressing:

$$\text{Force per mm} = P/\varepsilon = 124700/570$$

$$= 219 \text{ N/mm}$$

Force for live end slippage + temperature correction + 1/2 anchorage movement (or bed shortening) = (8 mm + 20 mm + 6.23 mm) x 219 = 7446 N

Total load = specified load + pressure for live end slippage + temperature correction = 138000 + 7446



$$= 145446 \text{ N}$$

Similar corrections should be made if stressing is done on a very warm day. The temperature of the steel on beds may approximate 45 C on a warm day, while the concrete temperature may be in the range of 20 C to 25 C. The resulting reduction in the steel temperature will result in an increase of tensile stresses in the steel. One is usually able to predict the temperature of the fresh concrete with sufficient accuracy to calculate the temperature change expected on the steel at the time the concrete is placed.

1029.3.7 Placement of Reinforcement. The inspector shall insure that the placing and tying of reinforcing bars conform to the applicable requirements of Specification Sec 706 and that all reinforcing steel and prestressing strands are properly placed and are clear and free. All reinforcing steel shall be checked to insure that it is free from form oil or other material that might serve as a bond breaker.

1029.3.7.1 Deck Panel. The reinforcing steel shall be tied securely to the strands with the following maximum spacing:

#3–P2 bars at 16 inches

Welded wire fabric or welded deformed bar mats at 24 inches in each direction.

The #3–U1 bars shall be tied to the #3–P2 bars, or to the welded wire fabric, or to the welded deformed bar mats, at about 36 inches in each direction.

1029.3.8 Placing and Consolidating Concrete. The inspector shall insure that the placing, finishing, and consolidating of concrete is in accordance with the applicable provisions of Specification Sec 703 with the following revisions:

- (a) Not more than 30 minutes should be permitted between the placing of contiguous lifts of concrete.
- (b) During hot weather, special precautions shall be taken. The mixed concrete when placed should have a temperature no higher than 90 F [32 C]. The forms and reinforcing steel shall be cooled by acceptable methods to 90 F [32 C] or lower.
- (c) Fabricating plants with demonstrated facilities for protection of the concrete during cold weather may, with the approval of the engineer, cast prestressed bridge superstructure units when the air temperature is below 45 F [7 C]. When the air temperature is below 40 F [4 C] the forms or enclosures shall be preheated to attain a temperature of at least 40 F [4 C]. No concrete shall be placed when the air temperature is below 35 F [2 C]. The temperature of the mixed concrete when placed shall not be lower than 60 F [15 C].
- (d) The concrete for each member should be placed in a minimum of two continuous lifts. The thickness of the first layer for prestressed I beam sections should be such that the top of the concrete is slightly above the top of the bottom fillet. The casting procedure should be modified when the length of members and placement conditions are such that a cold joint may result if each lift is continued full length before another lift is placed.



1029.3.8.1 Concrete Testing. During the placement of the portland cement concrete, tests shall be performed by the inspector to insure that the requirements of Specification Sec 1029.3.10 are met. Portland cement concrete shall be inspected in accordance with [Field Sec 501](#) of this Manual and Sec 500 of the Construction Manual. Tests for determining consistency and air entrainment shall be performed. At least 3 sets of specimens for compressive strength shall be prepared for each casting operation in each line of curing enclosure. When compressive strength for release is not needed, such as curbs on double tees, at least 2 sets shall be prepared. In any case, a sufficient number of cylinders shall be made throughout the pour to assure the engineer that each unit(s) or portion thereof achieve minimum required compressive strength. Specimens shall be prepared in accordance with Sec 501.16.5 of the Construction Manual or vibrated. If vibrated, cylinder molds shall be filled in two equal lifts. Vibrate each lift only enough to achieve proper consolidation of the concrete. In compacting the specimen, the vibrator shall not be allowed to rest on the bottom or sides of the mold. Carefully withdraw the vibrator in such a manner that no air pockets are left in the specimen. After vibration of each layer, tap the sides of the mold with the mallet to ensure removal of large entrapped air bubbles. The ratio of the diameter of the cylinder to the diameter of the vibrating element shall be 4.0 or higher. Concrete with 3 inches [75 mm] or more slump will be rodded only. The fabricator shall furnish a sufficient number of compressive test cylinder molds meeting the approval of the engineer and shall furnish the manpower necessary for cleaning and preparing reusable molds. Four inch by eight inch (4" x 8") cylinders may be used for the acceptance of pre-cast concrete. The cylinders must be prepared in accordance with AASHTO T-23 (note Rod size and length, number of lifts, etc.). The compressive strength result must be multiplied by 0.94 before it is compared to the applicable requirement because small cylinders will break to indicate a compressive strength that is falsely high. Small cylinders are more sensitive to handling and curing conditions and are not generally suitable for use at a project site.

1029.3.8.2 Coring. In the event that all test cylinders have been tested and the required strength has not been achieved, the castings may be cored at the expense of the producer for further testing, if requested in writing by the producer. Two cores shall be taken from each casting for which strength determination is required. Obtaining and testing cores shall be performed according to AASHTO T 24. In addition, contact with reinforcement or strand is cause for rejection of the casting. The compression testing of the cores shall be done by an independent testing laboratory at the expense of the producer, with a copy of the report furnished to the engineer. If a core is damaged during the coring process, an additional core may be cut from the casting. The core holes are to be patched with approved patching materials. Both cores from any casting shall exceed the required strength or the casting shall be rejected. The coring process to determine compressive strength shall be performed only once on any casting.

1029.3.9 Curing. The inspector shall observe the curing operation to verify that the requirements of Specification Sec 1029.6.11 are met. Concrete members shall be kept continuously wet until the conclusion of the curing period. Curing shall be accomplished by covering with burlap or jute mats kept continuously wet, by a moist air or live steam method, or any combination of these methods. Other moist curing methods may be used, provided the details of the proposed method are submitted to the engineer and approved. As soon as the concrete has set sufficiently that no marring of the surface or distortion will result, wet burlap or jute mats shall be applied in contact with the exposed surface. The burlap or jute mats shall be sufficiently wet to prevent moisture absorption by the burlap from the finished surface. The concrete shall not be exposed to temperatures below freezing until the curing has been completed. Curing in accordance with Specification Sec 1029.6.11 shall be



continued until the concrete has attained the design compressive strength shown on the plans. When test cylinders from different batches of concrete are used to determine design compressive strength, each cylinder tested shall obtain the minimum required compressive strength. The compressive strength of the concrete at stress transfer or post-tensioning is to be determined by testing cylinders cured by the exact methods used to cure the concrete members. The cylinders should be placed in regions representing the average curing conditions on the member.

1029.3.9.1 Steam Curing. A preset period of not less than 4 hours should be allowed before the steam cure is applied. However, when the ambient temperature is below 50 F [10 C] steam should be applied also during the preset period, but only at a rate sufficient to keep the air surrounding the beam at a temperature between 50 [10 C] and 70 F [20 C]. Steam shall be applied from pipes with perforations at suitable intervals laid along each side of the member, or by other approved arrangement. Jets of steam shall not be permitted to impinge directly against the member, forms, or test specimens. Provisions shall be made for effective circulation of the steam around all portions of the members. The steam shall be thoroughly saturated at all times. If dehydration of the concrete or perceptible drying of the wet burlap initially placed on the concrete is noted, soaker hoses placed on top of the members, or other approved methods should be used to supply sufficient moisture during the steam-curing period. After the preset period, steam shall be applied at a rate that will not increase the temperature of the air surrounding the members faster than 40 F [20 C] per hour. The maximum curing temperature shall not exceed 160 F [70 C] and the difference in temperature adjacent to the concrete at different locations within the enclosure shall not exceed 30 F [20 C] at any time. Fluctuations of the temperature adjacent to the concrete during the curing period at any one location shall not vary more than 30 F [20 C]. The contractor shall furnish, and place at the direction of the inspector a minimum of two portable recording thermometers, and not less than one for each 150 feet [50 m] of enclosure, for use in determining the magnitude and degree of uniformity of temperatures within the enclosure. The temperature recording system shall be capable of automatically producing a temperature record during the entire curing period. The temperature record shall show the temperature at each location at intervals of not more than 15 minutes and have a range of approximately 0 to 200 F [-20 C to 100 C]. Any unit, when calibrated, individually should be accurate within plus or minus 5 F [2 C]. The steam curing should continue until the required strength for transfer of prestress has developed. After the expiration of the steam-curing period, the temperature inside the chamber shall be reduced at a rate of not more than 40 F [20 C] per hour until a temperature has been reached about 40 F [20 C] above the temperature of the air to which the concrete will be exposed.

1029.3.10 Form Removal. Forms should not be stripped from prestressed concrete members sooner than 12 hours after pouring. If forms are removed before the concrete has attained the strength which will permit the units to be moved or stressed, only the minimum area of the curing enclosure that is necessary to remove each individual form section should be removed at any one time. The open area in the enclosure should be immediately closed as each form section is removed. When the surrounding air temperature is below 30 F [-1 C], no portion of the enclosure should be removed before the unit has attained the required transfer strength. Cylinder forms shall be stripped at the same time the forms are removed from the members.

1029.3.11 Surface Finish. The inspector shall insure that surface finish is in accordance with the requirements of Specification Sec 703 and 1029 as applicable. The engineer will determine the kind, type, and extent of cracks and surface defects such as honeycomb and



chipped edges or corners that will be tolerated except that, the outer surface of each outside beam shall have a smooth, uniform surface when removed from the forms or shall be immediately finished to achieve a smooth, uniform surface. Repairs may be permitted with mortar in accordance with Specification Sec 703.3.2.9. Commercially available patching materials shall be used only when approved by the engineer. The top surface of members which will become a part of the roadway surface shall be scored transversely to a depth of approximately 1/4 in. [5 mm] with a wire brush, stiff broom, or other approved method unless otherwise specified in the contract. No laitance should remain on the surfaces to be embedded in the concrete. The end portions of members to be embedded in the diaphragms should be roughened by sandblasting or other approved methods to provide suitable bond between the member and diaphragm unless otherwise specified in the contract. Depressions left in pretensioned members with draped strands, after removal of hold-down devices, should be plugged. If the method for plugging these holes is not covered in the shop drawings, written approval of the proposed method shall be obtained. Exposed reinforcing steel should be thoroughly cleaned of all concrete before delivery of members.

1029.3.12 Prestress Transfer. The required cylinder strength of concrete at transfer of the tensioning load shall be that shown on the approved drawings. When test cylinders from different batches of concrete are used to determine strand release, each cylinder tested shall obtain the minimum required compressive strength. Compressive tests are to be performed, in accordance with Sec 501.16.5 of the Construction Manual, at the fabricating plant. If questionable results are obtained, the specimens may be submitted to the Central Laboratory. At least one set of regular 28 day cylinders should be submitted to the Central Laboratory for each project to check the portland cement concrete mix design with a minimum of one set per month of operation or as often as deemed necessary. SiteManager is to be used to identify cylinder sets submitted to the central lab. If steam curing was used, strand release should be performed while the members are still warm. Forms which may restrict movement of the members should be removed or loosened prior to strand release. The sequence for releasing the strands and hold down devices shall be in accordance with approved shop drawings. Strand release should be observed routinely to assure that the specified sequence is being used and that damage is not occurring to the units during release and subsequent handling.

1029.3.13 Inspection of Completed Members. The completed members shall be inspected after release of the strands, and while they are still on the casting bed, to determine their acceptability. At least one end of each beam shall be raised clear of the bed and lowered before making camber measurements. Camber is defined as the upward deflection which occurs in prestressed concrete flexural members due to net bending resulting from the combination of moments due to stressing forces and dead load. Uniform camber, conforming closely to computed values, is evidence of good quality control. Excessive camber for members on the same bed is usually an indication of low concrete strength. Wide camber variations in similar products indicate poor quality control during manufacture. These differential cambers can result from differential tension in strands as a result of many hold-down points, very steep drapes, non-uniform curing, or poor control of concrete batching, mixing, placing, or consolidating.

1029.3.13.1 Dimensional Tolerances. If definite tolerances are not specified in the contract, the tolerances shown in the applicable table of Specification Sec 1029.7 shall be used by the inspector. If the members vary from these tolerances, the State Construction and Materials Engineer shall be consulted. Assistance in determining measurement of



tolerance is provided in Exhibit 1029-B.

1029.3.13.2 Marking. The inspector shall insure that each member is identified with the date, manufacturer, identification number, and load design when applicable. These markings may be indented on the member or painted thereon with waterproof paint. These markings shall be located as shown on the plans. If the location of the markings are not shown on the plans, they shall be located in such a manner that they will not be obvious or objectionable to the traveling public after the member has been placed in its final position. Accepted members are to be stamped with an "OK - MoDOT" by the inspector.

1029.3.13.3 Deck Panel Cracking. The inspector shall inspect the prestressed deck panel for cracking. Most cracking is unacceptable; however, certain cases of hairline cracks may be accepted. Hairline cracks are defined as very fine to nearly invisible, with no spalling of material along the crack, and may be more visible when the concrete is wet. Inspection shall be performed by visual examination without the addition of water to exaggerate the presence of the crack. Hairline cracks may be accepted, provided not more than one crack extends the entire span of the panel, the crack runs generally parallel to the strands, and there are not more than two cracks originating from any point. A maximum of three cracks may run from both strand edges of the panel toward the middle, with not more than one all the way from edge to edge, and any remaining cracks no further than the quarter points of the panel. Panels that are cracked as a result of obvious physical abuse, e.g. dropped or otherwise marred are not acceptable. Any questionable panels shall not be accepted until Headquarters has been consulted. Exhibit 1029-A shows the worst case panel that may be accepted.

1029.3.14 Handling, Storing and Transporting. The handling and storage of prestressed members shall be in accordance with Specification Sec 1029.6.3. In storage, I-beams should be fully supported across their width on battens that are not less than 4 inches [100 mm] wide. During transportation, the ends of I-beams should not extend a distance of more than the depth of the beam beyond the bolsters or other supports on the transporting vehicle. Deck beams should not extend more than 1-1/2 times their depth beyond the supports on the transporting vehicle. During storage, the supports shall maintain the members in essentially a level position without twisting. Stacking of the members in storage will be permitted only with the approval of the engineer. If such permission is granted, the supports of all members shall be in the same vertical planes and shall be of adequate thickness to prevent damage to the lifting devices.

1029.3.15 Records. The plant inspector shall maintain a complete file of all data pertaining to the manufacture of the concrete units, either at the manufacturing plant or in the District office. Complete and accurate records of each manufacturing operation shall be kept in a field book. All pertinent data which in any way affects or influences the construction procedures or completed members including identification, camber and measurements required to determine acceptability for all members shall be recorded in the field book. Data shall be entered in the field book as soon as it is known. Field notes should not be copied but shall be kept exactly as they are originally recorded.

1029.4 REPORT.

1029.4.1 Materials shall be reported as shown in the corresponding sections of this Manual. Prestressing strands and structural steel, if required, shall be reported through SiteManager. The form shall show all pertinent information regarding the material and a copy of the



certification shall be attached to the district copy, where it should be retained. The report is to indicate acceptance, qualified acceptance, or rejection. Appropriate remarks as described in [General Sec 7](#) of this Manual, are to be included in the report to clarify conditions of acceptance or rejection.

1029.4.2 Distribution of the reports is to be as shown in the corresponding sections of this Manual except that the copies normally forwarded to the Resident Engineer shall be furnished to the inspector at the precast manufacturing plant. The reports shall be marked "General" and the name of the precast concrete manufacturer must be shown. The material is to be shown for use in "Precast Concrete Units." The plant inspector located at the concrete proportioning plant shall furnish a plant inspector's daily report in SiteManager for each day's pour identifying the units manufactured from that pour. The name of the manufacturer or set-up must be shown. The original copy of this report shall be forwarded to the State Construction and Materials Engineer. The duplicate copy shall be furnished to the district Operations Engineer supervising operations at the manufacturing plant. The triplicate copy shall be retained by the plant inspector for the plant records.

1029.4.3 When precast concrete units are delivered to a given project, SiteManager samples shall be completed with distribution of reports per Class A in [General Sec 7](#).

Distribution of reports for materials purchased under a Department purchase order is to be as described in [Field Sec 2001](#) of this Manual.






Exhibit 1029-A

Where Distance S = Length of the Panel



MATERIALS

TOP VIEW





Exhibit 1029-B1

END VIEW
Exhibit 1029-B2



SIDE VIEW





Exhibit 1029-B3




Top View



Lifting Loop

Side View



Exposed Beam End
(Deviation from Square)

End View

